

LEGAL DESCRIPTION:

LIBER

& rc

19

THAT PART OF THE EAST 55 ACRES OF THE NORTH 1/2 OF THE NE 1/4, SECTION 34, T1N,R1E, BUNKERHILL TOWNSHIP, INGHAM COUNTY, MICHIGAN, EXCEPT THE SOUTH 24 RODS THEREOF.

HEREIN SURVEYED AND DESCRIBED AS: BEGINNING AT THE NE CORNER OF SAID SECTION 34, THENCE SOUTH ALONG THE EAST LINE OF SAID SECTION, 234.00 FEET; THENCE WEST 220.00 FEET; THENCE SOUTH 260.00 FEET; THENCE EAST 220.00 FEET TO THE EAST LINE OF SECTION 34; THENCE SOUTH ALONG SAID EAST LINE, 427.66 FEET; THENCE S89°56'54"W ON A LINE PARALLEL AND 24 RODS (396 FEET) NORTH OF THE SOUTH LINE OF THE NORTH 1/2 OF THE NE 1/4 OF SAID SECTION, 1813.14 FEET; THENCE NOO°05'57"W ON THE WEST LINE OF SAID EAST 55 ACRES OF THE NORTH 1/2 OF THE NE 1/4 OF SAID SECTION, 922.32 FEET TO THE NORTH LINE OF SECTION 34; THENCE N89°58'09"E ON SAID NORTH LINE, 494.74 FEET TO THE NW CORNER OF FITCHBURG CEMETERY; THENCE ALONG THE WESTERLY AND SOUTHERLY LINES OF SAID CEMETERY THE FOLLOWING COURSES: SOUTH, 165.00 FEET;

N89°58'09"E, 98.00 FEET;

SOUTH, 100.00 FEET:

AND N89°58'09"E, 498.92 FEET TO THE CENTERLINE OF McCREERY DRAIN; THENCE NORTHERLY ALONG SAID CENTERLINE OF McCREERY DRAIN THE FOLLOWING COURSES:

N74°55'48"E, 164.90 FEET; . N00°04'18"W, 94.95 FEET;

AND N34°22'21"W, 154.13 FEET TO THE NORTH LINE OF SECTION 34; THENCE N89°58'09"E ALONG SAID NORTH LINE, 650.99 FEET TO THE POINT OF BEGINNING. CONTAINING 32.91 ACRES AND SUBJECT TO THE NORTH 33 FEET AND THE EAST 33 FEET FOR USE AS PUBLIC RIGHT-OF-WAY AND TO ANY OTHER ENCUMBRANCES OF RECORD.

We hereby certify that we have surveyed the property herein described, and that there are no visible encroachments upon the above described property, except as shown hereon.

We further certify that we have fully complied with the requirements of Section 3, Public Act 132 of 1970, and that the ratio of error of closure

LEGEND

- O Set Iron
- Found imp

4365

- Fence Line
- R Recorded Distance
- M Measured Distance
- D Deeded Distance

RON HELSEL, R.L.S. No. 18994



ACCOLADE, INC.

Land Surveying and Planning Specialists 807 Kerns Rd., Suite 101, Mason, Mich. 48854 P.O. Box 144 Phone 517-676-7580

DUANE YERKS STOCKBEIDEE, MI

FIELD NDIDW 4-22-93	DATE 30 APE. 1993
DRAWN D.P. 4.30.93	SURVEY NO. 93.4567
CHECKED PH 5.3.93	SHEET 2 OF: 2

-- The South of th

ERTIFICATE OF SURVEY

LEGAL DESCRIPTION:

LIZER

THAT PART OF THE SOUTHWEST 1/4 OF THE SOUTHWEST 1/4 OF SECTION 35, T1N,R1E, BUNKERHILL TOWNSHIP, INGHAM COUNTY, MICHIGAN HEREIN SURVEYED AND DESCRIBED AS:

PARCEL A

BEGINNING ON THE SOUTH LINE OF SECTION 35, T1N,R1E, BUNKERHILL TOWNSHIP, INGHAM COUNTY, MICHIGAN AT A POINT 468.62 FEET (MEASURED: 466.42 FEET), EAST FROM THE SOUTHWEST CORNER OF SAID SECTION 35; THENCE WEST ALONG THE SOUTH LINE OF SAID SECTION, 16.21 FEET; THENCE N00°13'20"W, 285.00 FEET; THENCE EAST, 16.21 FEET; THENCE S00°13'20"E, 285.00 FEET TO THE POINT OF BEGINNING. CONTAINING 0.106 ACRES, SUBJECT TO THE SOUTH 33 FEET FOR USE AS A PUBLIC RIGHT-OF-WAY AND TO ANY OTHER ENCUMBRANCES OF RECORD.

PARCEL B

BEGINNING AT A POINT 468.62 FEET (MEASURED: 466.42 FEET), EAST ALONG THE SOUTH LINE OF SECTION 35, T1N,R1E, BUNKERHILL TOWNSHIP, INGHAM COUNTY, MICHIGAN, AND 285.00 FEET, N00°13'20"W FROM THE SOUTHWEST CORNER OF SAID SECTION 35; THENCE CONTINUING N00°13'20"W, 165.00 FEET; THENCE EAST, 28.00 FEET; THENCE \$00°13'20"E, 165.00 FEET; THENCE WEST, 28.00 FEET TO THE POINT OF BEGINNING. CONTAINING 0.106 ACRES, SUBJECT TO ANY ENCUMBRANCES OF RECORD.

SOUTHWEST CORNER

FOUND 1" BAR 0.5' NORTH FROM THE NORTHERLY ASPHALT EDGE OF BASELINE ROAD.

SECTION 35, T1N,R1E

SET NAIL & TAG No. 18994 IN SOUTH SIDE OF 20" WALNUT: N40°E, 47.08" SET NAIL & TAG No. 18994 IN WEST SIDE OF 30" WILLOW: N10°F, 206,00" SET NAIL & TAG No. 18994 IN NORTH SIDE OF 6" CEDAR: \$45°W, 49,94"

FOUND 3/4" PIN: N10°W, 4.85"

SOUTH 1/4 CORNER SECTION 35, T1N,R1E FOUND 1/2" BAR AND CAP No. 18998 IN 4" CONCRETE MONUMENT. FOUND NAIL AND TAG No. 18998 IN WEST SIDE OF 10" WALNUT: N50°W, 48.48'

FOUND NAIL AND TAG No. 18998 IN NORTH SIDE OF 6" OAK: \$45°W, 44.57 FOUND NAIL AND TAG No. 18998 IN WEST SIDE OF 6" OAK: SOUTH, 26.46" FOUND NAIL AND TAG No. 18998 IN WEST SIDE OF 6" ASH: S30°W, 34.25"

DEED: 194.00' _ APPROXIMATE - FOUND 5/8" REBAR WATER'S EDGE EAST 28.00 PARCEL B RECORDED 0.106 AC. 90 Nov 15 11 32 AM 'SH EAST RESISTER OF BEEDS 16.21 Œ: 1 IN. 100 FT WEST Dande O+ haire 28,00 THEHAM COURTY MICHA P.O.B. 'B' NOTE: BEARINGS ARE RECATIVE TO THE SOUTH SECTION LINE BEING DEEDED AS EAST ! " E "WEST." .00.51 ,02,51,00 ó WEST SOUTHEAST CORNER ò SOUTH 14 CORNER SECTION 35 SECTION 35 TIN, RIE PARCEL A TIN, DIE LIBER 4, PAGE 94 0.106 AC. LIBER 6, PAGE 195 FOUND 34" PIN found 5/8" rebar 0.84' WEST ! FOUND BAR! 33' ROW.) 4.78 NORTH CAP No. 21275 WEST SOUTH LINE, SEC. 35 16.21 194.00 EAST DEED: 468.62 2164.78 MEAS: 466.42' POB "A" BASELINE

We hereby certify that we have surveyed the property herein described, and that there are no visible encroachments upon the above described property, except as shown hereon.

We further certify that we have fully complied with the requirements of Section 3, Public Act 132 of 1970, and that the ratio of error of closure of this survey is no greater than 1/5000.

MICHIG

LEGEND

- O Set Iron & CAP No. 18994
- Found from
- 🗻 Fence Line
- R Recorded Distance
- M Measured Distance
- D Deeded Distance

RON HELSEL LAND AREA LAND Surveyor RON HELSEL, R.L.S. No. 18994

of


ACCOLADE, INC.

Land Surveying and Planning Specialists 807 Kerns Rd., Suite 101, Mason, Mich. 48854 P.O. Box 144 Phone 517-676-1580

DALE RISNER 1511 BASELINE ROAD

STOCKBRIDGE, MICHIGAN 49285

FIELD MP/CK 10-19-94 DATE OCT. 21, 1994 DRAWN & SURVEY NO. 94 . 6371 10.21.94 SHEET | OF: (10-21-94 EH



2 N 307 LIB

PARCEL #1 - A part of the E 1/2 of the W 1/2 of the SE 1/4 of Section 26, TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of . Fitchburg Road, said line also being the South line of said Section, 1763.36 feet to the point of beginning of the parcel to be described; thence continuing due West, along said centerline and said section line, 210.55 feet; thence N.00°17'39'W., 2638.03 feet to the East - West 1/4 line of said section, thence S.89°55'49"E., along said 1/4 line, 345.55 feet; thence S.00°17'39"E., 2314.94 feet; thence due West, 135.00 feet; thence S.00°17'39"E., 322.67 feet to the point of beginning, containing 19.92 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

PARCEL #2 - A part of the E 1/2 of the W 1/2 of the SE 1/4 and a part of the W 1/2 of the E 1/2 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows, Commencing at the SE 1/4 of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1384.94 feet to the point of beginning of the section line, 243.42 feet; thence ontinuing due West along said centerline and said line of said Section; thence S.89°55'49"E., along said 1/4 line, 312.72 feet; thence S.00°17'16"E., 1317.23 feet; thence due East 66.00 feet; thence S.00°17'16"E., 997.33 feet; thence due West 135.00 feet; thence S.00°17'16"E., subject to the point of beginning, containing 19.92 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

PARCEL #3 - A part of the E 1/2 of the W 1/2 of the SE 1/4 of Section 26, TIN-RIE Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing Bunker Hill Township, ingham county, Michigan, described as tollows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road said line also being the South line of said Section, 1628.36 feet to the point of beginning of the Parcel to be described; thence continuing due West along said centerline and said section line, 135.00 feet; thence N.00°17'39"W., 322.67 feet; thence due East, 135.00 feet; thence S.00°17'39"E., 322.67 feet to the point of beginning, containing 1.00 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

PARCEL #4 - A part of the E 1/2 of the W 1/2 of the SE 1/4 and a part of the W 1/2 of the E 1/2 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1249.94 feet to the point of beginning of the Parcel to be described; thence continuing, due West along said centerline and said section line, 135.00 feet; thence N.00°17'16"W., 322.67 feet; thence due East 135.00 feet; thence S.00°17'16"E., 322.67 feet to the point of beginning, cover the existing Fitchburg Road. over the existing Fitchburg Road.

NE CORNER, Section 26, 3/4" pipe fd. N.25°W. 80.05 Nail fd. E/S 8" tree S.15°W. 132.03 Nail fd. E/S 18" tree S.65°W. 71.59 Nail fd. E/S 12" tree

CENTER SECTION, Section 26, 1/2" rerod set at fence intersection

S.51°E 156.50 Nail W/S Dbl. tree S.16°E. 231.37 Nail W/S 24" dbl. tree S.89°W. 14.00 Nail top sq. fence post

SW CORNER, Section 26, 1/2" pipe fd. N.45°W. 80.5 SE corner porch N.45°E. 146.12 SW corner house S.20°W. 59.33 Nail E/S 20" Elm

SE CORNER, Section 26, 1/2" sq. rod fd. N.41°E. 42.68 Nail fd. E/S 24" tree N.38°W. 47.25 Bolt fd. S/S t.p. N.71°W. 67.60 P.K. fd. S/S t.p. S.23°E. 47.17 P.K. fd. NE/S't p. S.23°E. 47.17 P.K. fd. NE/S t.p.

REFERENCE: 1 Warranty Deed as recorded Liber 1107, Page 800, Ingham County Records 2 Quit Claim Deed as recorded Liber 1125, Page 320 Ingham County Records

HEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

February 6, 1975

I seen Boss REGISTERED LAND SURVEYOR 13574

CLIENT **JONES** DESCRIPTION Part of the SE 1/4

SECTION 26 T. 1N-R. 1E TOWNSHIP Bunker Hill LEGEND

O = IRON SET IRON FOUND NAIL SET A = MONUMENT FOUND FENCE


BOSS ENGINEERING COMPANY CIVIL ENGINEERS - LAND SURVEYORS

3121 E. GRAND RIVER, HOWELL, MICHIGAN (517) 546-4836 48843 906 S. BRIDGE ST. CHARLEVOIX, MICHIGAN (616) 547-2872 49720

SCALF: SHEET 1''.= 200 DR. BY: S.R.M. JOB NO. 5319 DATE: CHKD BY: / HW



RECORDED



DESCRIPTION FURNISHED BY ARRON CRAFT

Comm. 16 2/3 rds. m/l W of NE cor. of W 1/2 of NW 1/4 of Sec. 36, TlN, RlE, at a pt. wherein existing fenceline now stands, then S along fence 92 rds., then W 37 rds., N 92 rds., RECORDING SPACE E 37 rds to p.o.b. Excepting therefrom a parcel of land 20' E and W by 323.5 ft. N and S located in the NW cor. of above described parcel.

DESCRIPTION, PARCEL #1

Comm. at a pt. distant E 1,031.28 ft. and S 00° 32' 53" W 1,155.00 ft. from the NW cor. of Sec. 36, TlN, RlE, Bunkerhill Township, Ingham County, Michigan; thence N 89° 59' 49" W 588.54 ft., S 00° 41' 06" W 363.00 ft., S 89° 59' 46" E 589.41 ft., N 00° 32' 53" E along the Old Existing Fenceline 363.00 ft. to the p.o.b. Containing 4.910 acres more or less.

DESCRIPTION, PARCEL #2

Comm. at a pt. distant E 1,031.28 ft. from the NW cor. of Sec. 36, TlN, RlE, Bunkerhill Township, Ingham County, Michigan; thence S 00° 32' 53" W along the Old Existing Fenceline 1,155.00 ft., N 89° 59' 49" W 436.61 ft., N 00° 41' 06" E 825.01 ft., E 194.57 ft., N 00° 41' 06" E 330.00 ft., E 239.28 ft. to the p.o.b. Containing 10.07 acres more or less.

DESCRIPTION, PARCEL #3

Comm. at a pt. distant E 627.00 ft. from the NW cor. of Sec. 36, TlN, RIE, Bunkerhill Township, Ingham County, Michigan; thence S 00° 41' 06" W 330.00 ft., E 165.00 ft., N 00° 41' 06" E 330.00 ft., W 165.00 ft. to the p.o.b. Containing 1.25 acres more or less.

DESCRIPTION, PARCEL #4


Comm. at a pt. distant E 627.00 ft. from the NW cor. of Sec. 36, TlN, RIE, Bunkerhill Township, Ingham County, Michigan; thence S 00° 41' 06" W 330.00 ft., W 29.57 ft., S 00° 41' 06" W 825.01 ft., N 89° 59' 49" W 151.93 ft.W16.50ft N 00° 41' 06" E 528.00 ft., E 33.00 ft., N 00° 41' 06" E 627.00 ft., E 165.00 ft. to the p.o.b. Containing 4.22 acres more or less.

I certify that I have surveyed the property described hereon and that the ratio of error of closure on the unadjusted field measurements is not greater than 1/5000, and that all of the requirements of P.A. 132 of 1970 have been complied with.

Bearings were referenced to the North Section Line of Section 36, which is assumed to bear due East and West.

WOLVERINE ENGINEERING COMPANY

George M. Young R.L.S. # 17640



LEGEND


SECTION LINE
DESCRIBED BOUNDARY
IRON SET & CAPPED
CORNER ANCHOR POST
IRON FOUND
SECTION OR 1/4 CORNER

WOLVERINE ENGINEERING COMPANY
ENGINEERS SURVEYORS
MASON, MICHIGAN

SURVEY FOR ARRON CRAFT

FLD. SURVEY 123,24-76 SCALE 1"=200"

DRAWN BY R.S. CLARK DATE 2-12-75



NOTE: Descriptions superceed descriptions Recorded at Ingham County Register of Deeds, Liber 2, Page 325.

DESCRIPTION FURNISHED BY ARRON CRAFT

RECORDING SPACE

Comm. 16 2/3 rds. m/l W of NE cor. of W 1/2 of NW 1/4 of
Sec. 36, TlN, RlE, at a pt. wherein existing fenceline now stands, then S
along fence 92 rds., then W 37 rds., N 92 rds., E 37 rds. to p.o.b. Excepting
therefrom a parcel of land 20 ft. E and W by 323.5 ft. N and S located
in the NW cor. of above described parcel.

DESCRIPTION, PARCEL #1

Beg. at a point distant E along the N sec. line 462.00 ft. from the NW cor. of Section 36, TlN, RlE, Bunkerhill Township, Ingham County, Michigan, thence E along said sec. line 165.00 ft., S 00° 41' 06" W 330.00 ft., W 165.00 ft., N 00° 41' 06" E 330.00 ft. to the p.o.b. Containing 1.25 acres more or less.

DESCRIPTION PARCEL #2

Beg. at a point distant E along the N sec. line 792.00 ft. from the NW cor. of Section 36, TlN, RlE, Bunkerhill Township, Ingham County, Michigan, thence S 00° 41' 06" W 330.00 ft., W 165.00 ft., N 00° 41' 06" E 330.00 ft., E along said sec. line 165.00 ft. to the p.o.b. Containing 1.25 acres more or less.

DESCRIPTION PARCEL #3

Beg. at a point distant E along the N sec. line 792.00 ft. from the NW cor. of Section 36, TlN, RlE, Bunkerhill Township, Ingham County, Michigan, thence E along said section line 165.00 ft., S 00° 41' 06" W 330.00 ft., W 165.00 ft., N 00° 41' 06" E 330.00 ft. to the p.o.b. Containing 1.25 acres more or less.

DESCRIPTION PARCEL #4


Beg. at a point distant E along the N sec. line 1,031.28 ft. from the NW cor. of Section 36. TlN, RlE, Bunkerhill Township, Ingham County, Michigan, thence S 00° 32' 53" W along the existing fence line 1,518.00 ft., N 89° 59' 46" W 589.41 ft., N 00° 41' 06" E 363.00 ft., W 16.50 ft., N 00° 41' 06" E 528.00 ft., E 33.00 ft., N 00° 41' 06" E 297.00 ft., E 495.00 ft., N 00° 41' 06" E 330.00 ft., E along N sec. line 74.28 ft. to the p.o.b. Containing 16.70 acres more or less.

I certify that I have surveyed the property described hereon and that the ratio of error of closure on the unadjusted field measurements is not greater than 1/5000, and that all of the requirements of P.A. 132 of 1970 have been complied with.

Bearings were referenced to the North section line of Section 36, which is assumed to bear due East and West.

WOLVERINE ENGINEERING COMPANY

George M. Young, R.L.S. # 17640



LEGEND

SECTION LINE
DESCRIBED BOUNDARY
IRON SET & CAPPED
GORNER ANCHOR POST
IRON FOUND
SECTION OR 1/4 CORNER

WOLVERINE ENGINEERING COMPANY ENGINEERS SURVEYORS MASON, MICHIGAN

SURVEY FOR ARRON CRAFT

FLD. SURVEY 7-07-78 SCALE NO SCALE

DRAWN BY T.V.G. DATE 7-07-75

SW CORNER, Section 26, 1/2" pipe fd. N. 45°W. 80.5 SE corner porch N. 45°E. 146.12 SW corner house S. 20°W. 59.33 Nail E/S 20" Elm

RECORDED

Nov 6 1 45 PM '75


REGISTER OF DEEDS and M. ofens

INCHAM COUNTY, MICH.

NE CORNER, Section 26, 3/4" pipe fd. N.25°W. 80.05 Nail fd. E/S 8"tree S.15°W. 132.03 Nail fd. E/S 18" tree S.65°W. 71.59 Nail fd. E/S 12" tree

SE CORNER, Section 26 1/2" sq. rod fd. N.14°E. 42.68 Nail fd. E/S 24"

tree N.38°W. 47.25 Bolt fd. S/S t.p.



HEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

REGISTERED LAND SURVEYOR NO. 13574

FRUIN BOSS ENGINEERING COMPANY DESCRIPTION Part of the CIVIL ENGINEERS LAND SURVEYORS SE 1/4 of SE 1/4 3121 E. GRAND RIVER, HOWELL, MICHIGAN (517) 546-4836 SECTION 26 906 S. BRIDGE ST. (615) 547-2872 CHARLEVOIX. T. 1N-R. 1E MICHIGAN TOWNSHIP Bunker Hill 49720 LEGEND 1148 SHEET OF 1'' = 200'O = IRON SET JOB NO. 6053 Ş.R.M. NAIL SET MONUMENT FOUND 2 CHKO BY: JW - = FENCE September 26, 1979



PARCEL #1 - A prt of the SE 1/4 of the SE 1/4 of Section 2 TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Fitchburg Road, said line also being the South line of said Section, due West 1084.94 feet from the SE corner of said Section; thence continuing due West, 165.00 feet; thence N.00°17'16"W., 297.00 feet; thence due East 165.00 feet; thence S.00°17'16"E., 297.00 feet to the point of beginning, containing 1.12 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

PARCEL #2 - A part of the SE 1/4 of the SE 1/4 of Section 26, TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Fitchburg Road, said line also being the South line of said Section, due West 919.94 feet from the SE corner of said Section; thence continuing due West 165.00 feet; thence N.00°17'16"W., 297.00 feet; thence due East 165.00 feet; thence S.00°17'16"E., 297.00 feet to the point of beginning, containing 1.12 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

PARCEL #3 - A part of the SE 1/4 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Fitchburg Road, said line also being the South line of said Section due West, 754.94 feet from the SE corner of said Section; thence continuing due West 165.00 feet; thence N.00°17'16"W., 297.00 feet; thence due East, 165.00 feet; thence S.00°17'16"E., 297.00 feet to the point of beginning. containing 1.12 acres more or less and subject to the rights of the beginning, containing 1.12 acres more or less and subject to the rights of the public over the eixsting Fitchburg Road.

PARCEL #4 - A part of the SE 1/4 of the SE 1/4 of Section 26, TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at the SE corner of said Section; thence due West along the centerline of the SE corner of said Section; thence due west along the centerline of Fitchburg Road, said line also being the South line of said Section, 754.94 feet thence N.00°17'16"W., 297.00 feet; thence due East, 755.00 feet to the centerline of Friermuth Road, said line also being the East line of said Section; thence S.00°16'30"E., along said centerline of Friermuth Road, and said East line, 297.00 feet to the point of beginning, containing 5.15 acres more or less and subject to the rights of the public over the existing Fitchburg and

PARCEL #5 - A part of the SE 1/4 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, INgham County, Michigan, described as follows: Beginning at a point on the centerline of Friermuth Road, said line also being the East line point on the centerline of Friermuth Road, said line also being the East line of said Section, N.00°16'30"W., 297.00 feet from the SE corner of said Section; thence due West, 1250.00 feet; thence N.00°17'16"W., 400.00 feet; thence due East, 1250.09 feet to said centerline and said Section line; thence S.00°16'30"E., along said centerline and said Section line, 400.00 feet to the point of beginning, containing 11.48 acres more or less and subject to the rights of the public over the existing Friermuth Road.


REF. 1. Survey by Boss Eng. Co. #5319 as recorded in L-2 of Surveys, Page 306 -307, Ingham County Records.

I HEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

Tscar Doss ED L. REGISTERED LAND SURVEYOR **10.** 13574

A A A

CLIENT	LIC ACT NUMBER 132-1970.		NO. 13574
FRUIN DESCRIPTION Part of the	BOSS ENGINEEL	OF WILLIAM	
ob 1/4 of the SE 1/4	3121 E. GRAND RIVER (517) 546-4836	LAND SURVEYORS HOWELL, MICHIGAN 48843	CSOAR LOSS
SECTION 26 T.1N -R. 1E FOWNSHIP Bunker Hill	906 S. BRIDGE ST. CI (616) 547-2872	SUMMER S	
LEGEND • IRON SET 1148	SCALE: 1" = 200'	SHEET 2 OF 2	13574
• " NAIL SET	JOB NO. 6053	DR. BY: S.R.M.	Management of the second
# * MONUMENT FOUND # = FENCE	DATE: September 26, 1979	CHKO BY: JAW	-



PARCEL #6 - Part of the SE 1/4 of Section 26, TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Friermuth Road, said line also being the East line of said Section, N.00°16'30"W., 697.00 feet from the SE Corner of said Section; thence due West 1250.09 feet; thence N.00°17'16"W., 348.80 feet; thence due East 1250.17 feet to said centerline and said Section line; thence S.00°16'30"E., along said centerline and said Section line, 348.80 feet to the Point of Beginning, and containing 10.01 acres more or less and subject to the rights of the public over the existing Friermuth Road.

PARCEL #7 - Part of the SE 1/4 of Section 26, TIN-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Friermuth Road, said line also being the East line of said Section, N.00°16'30"W., 1045.80 feet from the SE Corner of said Section; thence due West 1250.17 feet; thence N.00°17'16"W., 274.20 feet; thence due West 66.00 feet; thence N.00°17'16"W., 71.63 feet; thence S.89°55'49"E., 1316.25 feet to said centerline and said Section line; thence S.00°16'30"E., along said centerline and said Section line; 344.23 feet to the Point of Beginning and containing 10.01 acres more or less and subject to the rights of the public over the existing Friermuth Road.

PARCEL #8 - Part of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Friermuth Road, said line also being the East line of said Section, N.00°16'30"W., 1390.03 feet from the SE Corner of said Section; thence N.89°55'49"W., 1316.25 feet; thence N.00°17'16"W., 331.25 feet; thence S.89°55'49"E., 1316.32 feet to said centerline and said Section line; thence S.00°16'30"E., along said centerline and said Section line, 331.25 feet to the Point of Beginning and containing 10.01 acres more or less and subject to the rights of the public over the existing Friermuth Road.

PARCEL #9 - Part of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Beginning at a point on the centerline of Friermuth Road, said line also being the East line of said Section, N.00°16'30"W., 1721.28 feet from the SE Corner of said Section; thence N.89°55'49"W., 1316.32 feet; thence N.00°17'16"W., 353.34 feet; thence S.89°55'49"E., 1316.40 feet to said centerline and said Section line; thence S.00°16'30"E., along said centerline and said Section line, 353.34 feet to the Point of Beginning and containing 10.68 acres more or less and subject to the rights of the public over the existing Friermuth Road.

- REF: 1. Survey by Boss Engineering Company, Job #5319 as recorded in Liber 2, of Surveys, Pages 306-307, Ingham County Records.
 - 2. Survey by Boss Engineering Company, Job #6053 as recorded in Liber 2 of Surveys, pages 528-529, Ingham County Records.

SE CORNER, Section 26 1/2" Sq. rod fd. N.14°E. 42.68 Nail fd. E/S 24" Tree N.38°W. 47.25 Bolt fd. S/S tele. pole N.71°W. 67.60 P.K. fd. S/S tele. pole S.23°E. 47.17 P.K. fd NE/S tele. pole

E 1/4 CORNER, Section 26 1/2" Iron set S.40°E. 44.92 Nail W/S 36" Oak N.35°E. 46.46 Nail W/S 18" Oak N.72°W. 29.15 Nail S/S 15" Ash SW corner, Section 26, 1/2" pipe N.45°W 80.5 SE corner porch N.45°E 146.12 SW corner house S.20°W 59.33 Nail E/S 20" Elm


Center Section, Section 26, 1/2"
re-rod set at fence intersection
S.51°E 156.50 Nail W/S Dbl. tree
S.16°E 231.37 Nail W/S 24"DBL.Tree
S.89°W 14.00 Nail top sq. fence
post.

HEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

REGISTERED LAND SURVEYOR

CLIENT BOSS ENGINEERING COMPANY FRUIN DESCRIPTION Part of CIVIL ENGINEERS LAND SURVEYORS the SE 1/4 3121 E. GRAND RIVER, HOWELL, MICHIGAN (517) 546-4836 48843 SECTION 26 T.IN -R. IE 906 S. BRIDGE ST. CHARLEVOIX, MICHIGAN (616) 547-2872 TOWNSHIP Bunker Hill 49720 LEGEND SCALF: SHEET • : IRON SET 1334 1" = 300' # IRON FOUND # NAIL SET 0 JOB NO. DR. BY: 6805 GJW MONUMENT FOUND DATE : CHKD BY: 6-30-76





Witnesses:

Parcel #2-A: A part of the E 1/2 of the W 1/2 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1414.94 feet to the Point of Beginning of the parcel to be described; thence continuing due West along said centerline and said Section line, 213.42 feet; thence N 00° 17' 39" W 2637.61 feet to the East-West line of said Section; thence S 89° 55' 49" E along said 1/4 line, 312.72 feet; thence S 00° 17' 16" E 1317.23 feet; thence due West 99.00 feet; thence S 00° 17' 16" E 1320.00 feet to the Point of Beginning, containing 15.92 acres more or less and subject to the rights of the public over the existing Fitchburg Pond the public over the existing Fitchburg Road.

Parcel #4-A: A part of the E 1/2 of the W 1/2 of the SE 1/4 and a part of the W 1/2 of the E 1/2 of the SE 1/4 of Section 26, T1N-RIE, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1249.94 feet to the Point of Beginning of the parcel to be described; thence continuing due West along said centerline and said Section line 165.00 feet; thence N 00° 17' 16" W 1320.00 feet; thence due East 165.00 feet; thence S 00° 17' 16" E 1320.00 feet to the Point of Beginning, containing 5.00 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

Reference: 1) Survey by Boss Engr. Co.,#5319, recorded in Liber 2, pages 306 & 307, Ingham County Records.

I HEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

SECTION 26

LEGEND

BOSS ENGINEERING COMPANY CLOSURE ERROR I/ CIVIL ENGINEERS LAND SURVEYORS DESCRIPTION Part of the SE 1/4 3121 E. GRAND RIVER, HOWELL, MICHIGAN (517) 546-4836 48843 906 S. BRIDGE ST. SECTION 26 JIN -R 1E TOWNSHIP Bunker H117 CHARLEVOIX, MICHIGAN (616) 547-2872 49720 SCALE: SHEET OF 1614 1"=200 O : IRON SET O : IRON FOUND O : MAIL SET JOB NO 8838 D.P.B. PONUMENT FOUND DATE: CHKD BY: Oct. 14, 197

REGISTERED LAND SURVEYOR NO. 17022 STATE OF MICHIGANITA

GARY R.

BOSS

SURVEYOR &


ENGINEER

NO.

A PROPERTY OF A

3 N 738

Note: This survey is re-recorded to delete the S 1/4 Cor. of Section 26, as it was not used or located in performing this survey.



Parcel #2-A: A part of the E 1/2 of the W 1/2 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1414.94 feet to the Point of Beginning of the parcel to be described; thence continuing due West along said centerline and said Section line, 213.42 feet; thence N 00° 17' 39" W 2637.61 feet to the East-West line of said Section; thence S 89° 55' 49" E along said 1/4 line, 312.72 feet; thence S 00° 17' 16" E 1317.23 feet; thence due West 99.00 feet; thence S 00° 17' 16" E 1320.00 feet to the Point of Beginning, containing 15.92 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

Parcel #4-A: A part of the E 1/2 of the W 1/2 of the SE 1/4 and a part of the W 1/2 of the E 1/2 of the SE 1/4 of Section 26, T1N-R1E, Bunker Hill Township, Ingham County, Michigan, described as follows: Commencing at the SE corner of said Section; thence due West along the centerline of Fitchburg Road, said line also being the South line of said Section, 1249.94 feet to the Point of Beginning of the parcel to be described; thence continuing due West along said centerline and said Section line 165.00 feet; thence N 00° 17' 16" W 1320.00 feet; thence due East 165.00 feet; thence S 00° 17' 16" E 1320.00 feet to the Point of Beginning, containing 5.00 acres more or less and subject to the rights of the public over the existing Fitchburg Road.

Reference: 1) Survey by Boss Engr. Co.,#5319, recorded in Liber 2, pages 306 & 307, Ingham County Records.

I MEREBY CERTIFY THAT I HAVE SURVEYED THE ABOVE DESCRIBED PROPERTY AND THAT SAID SURVEY FULLY COMPLIES WITH THE REQUIREMENTS OF PUBLIC ACT NUMBER 132-1970.

REGISTERED LAND SURVEYOR

Jones BOSS ENGINEERING COMPANY CLOSURE ERROR 1/ DESCRIPTION PART CIVIL ENGINEERS LAND SURVEYORS THE SEI/4 3121 E. GRAND RIVER, HOWELL, MICHIGAN (517) 546-4836 48843 SECTION ZE T.IN-RIVE 906 S BRIDGE ST. CHARLEVOIX, MICHIGAN (616) 547-2872 TOWNSHIP BUNKER HIL 49720 LEGENO SCALE: SHEET Z GEND:

C : IRON SET 1978

B : IRON FOUND

A : NAIL SET

B : MONUMENT FOUND OF 1"= 200 100 NO 8838 08. 8Y: D.P.B. erei, SS.CIAL: BTAD CHKO BY: SIZIN FENCE

GARY R.
BOSS
SURVEYOR & BURNER
NO.
17022
17022
17022


CERTIFIED BOUNDARY SURVEY

Charles E. Reme 1565 E. Base Line Road FOR Stockbridge, Michigan

LOCATION MAP (NO SCALE)

LEGEND.

- All dimensions are in feet and decimals thereof. $\frac{1}{2}$ bars with identification caps have been placed at all points marked $\frac{1}{2}$ unless otherwise noted.
- ø described boundary。
- ✓ fence line.
- All bearings are relative and are referenced to the West line of Section 35, TIN, RIE, which is assumed to bear North-South.



Williams

٠	-	-	-			1. 7.25		20.00	A west	100	7. 3	4.4	< 1.00 mg/s	36.5	317	4.4		A 2	, C.	>
۶			10		775 LO			38		30			Vot a	31474	2134		5 V.	19 A.	copper.	
ì	3.4		<i>P Y</i>	H.					w	1//	27		S	EC	3	5.4	11	(-)	P//	Ξ,
-		2356	40	1	12.77	4	(G. 5)													
Á					ED				440	7/	٠,٪	'n.		OB	7	11.73			14	
è		13		6.542	uffyrtige Kilde Sam	the restant	C 1004													, be
Š	ξ,			4												7	W. T	Y.		2.5
ď	0.865		40.0		1.4		9	1	15.50	271	- 1	3.	3		1 Page		100	43. Y	-	47

3 ft /8%

CERTIFIED BOUNDARY SURVEY

LEGAL DESCRIPTIONS:

Parcel I

A parcel of land being a part of the E & of the SW & of the SW & of Section 35, TlN, RIE, Bunkerhill Township, Ingham County, Michigan; more particularly described as commencing at the SW corner of said Section 35; thence \$89°53'E along the South line of said Section 35, 659.93' to the point of beginning of this description; thence NOO°11'20°E, 528.0'; thence \$89°53'E parallel with the South line of said Section 35, 165.0'; thence \$00°11'20°W, 528.0' to the South line of said Section 35; thence N89°53'W along the South line of said Section 35, 165.0' to the point of beginning. Contains 2.000 acres, more or less, and subject to the rights of the public over existing Base Line Road.

Parcel 2

A parcel of land being a part of the E $\frac{1}{2}$ of the SW $\frac{1}{4}$ of the SW $\frac{1}{4}$ of Section 35, T1N, R1E, Bunkerhill Township, Ingham County, Michigan; more particularly described as commencing at the SW corner of said Section 35; thence S89°53'E along the South line of said Section 35, 82h.93' to the point of beginning of this description; thence N00°11'20"E, 290.5'; thence S89°53'E parallel with the South line of said Section 35, 150.0'; thence S00°11'20"W, 290.5' to the South line of said Section 35; thence N89°53'W along the South line of said Section 35, 150.0' to the point of beginning. Contains 1.000 acres, more or less, and subject to the rights of the public over existing Base Line Road.

Parcel 3

A parcel of land being a part of the E $\frac{1}{2}$ of the SW $\frac{1}{4}$ of the SW $\frac{1}{4}$ of Section 35, TlN, RIE, Bunkerhill Township, Ingham County, Michigan; more particularly described as commencing at the SW corner of said Section 35; thence S89°53'E along the South line of said Section 35, 974.93' to the point of beginning of this description; thence N00°11'20"E, 290.5'; thence S89°53'E parallel with the South line of said Section 35, 150.0'; thence S00°11'20"W, 290.5' to the South line of said Section 35; thence N89°53'W along the South line of said Section 35, 150.0' to the point of beginning. Contains 1.000 acres, more or less, and subject to the rights of the public over existing Base Line Road.

Farcel &

A parcel of land being a part of the E $\frac{1}{2}$ of the SW $\frac{1}{4}$ of the SW $\frac{1}{4}$ of Section 35, TIN, RIE, Bunkerhill Township, Ingham County, Michigan; more particularly described as commencing at the SW corner of said Section 35; thence S89°53°E along the South line of said Section 35, II2½,93° to the point of beginning of this description; thence N60°11°20°E, 290.5°; thence S89°53°E parallel with the South line of said Section 35; thence N69°53°W along the South line of said Section 35; thence N69°53°W along the South line of said Section 35, 150.0° to the point of beginning. Contains 1.000 acres, more or less, and subject to the rights of the public over existing Base Line Road.

Parcel 5

A parcel of land being a part of the R 1 of the SW 1 of the SW 1 of Section 3.
Tin, RIE, Bunkerhill Township, Ingham County, Michigan; more particularly described as commencing at the SW corner of said Section 3; thence \$89°53'E along the South line of said Section 3, 1271,93' to the point of beginning of this description; thence NGO'11'20"E, 290.5'; thence NB9°53'M parallel with the South line of said Section 35, 150.6'; thence NOO'11'20"E, 237.5'; thence NB9°57'B parallel with the South line of said Section 35, 169.12'; thence North parallel with the West line of said Section 35, 792.0' to the E/W 1/8 line of said Section 35; therce \$890'5'E along the E/W 1/8 line of said Section 35, 657.5' to the N/S 1/8 line of said Section 35; thence South along the N/S 1/8 line of said Section 35, 1320.10' to the South line of said Section 35, house of said Section 35; thence South slong the N/S 1/8 line of said Section 35, house to the point of beginning. Contains 11.887 acres, more or less, and subject to the rights of the public over existing Base Line Road.

1822

WILLIAMS

Burveying .

11	1		100	
	CKO	nos Pl		4
Briefly.	in his	chique.	4885	4
PH.	517	176 S	53	
100		2007	77.00	120

	The state of the s
DRAWN 20178 SEC. 35 T.	
	CARLES OF STREET
	44.00
COMPUTED at 1/1/2 102/1/2/	THE STATE OF THE S
	建筑在 的全体被击
FED. SURVEY When 2043	
	1. 600 A SHEET SA
	A STATE OF THE STA

CERTIFIED BOUNDARY SURVEY TEET 3 % 483

WITNESSES TO U.S. PUBLIC LAND CORNERS

NW corner of Section 35, TIN, RIE

NA5°W 80.5' SE corner of porch NA5°E 146.12' SW corner of house S20°W 59.33' nail in E/S 20" Elm

SW corner of Section 35, TlN, RIE

Nail & cap in 12" Apple S45°W 96.40' Nail & cap in 21" Willow N10°E 207.12' P.K in 21" Walnut N30°E 47.10'

SE corner of Section 35, TIN, RIE

Nail & tag in 14" Ash S80°E 27.80° Nail & tag in 14" Box Elder S08°W 15.00° Nail & tag in anchor pole N40°W 81.25°

I hereby certify to the parties named hereon that we have surveyed five parcels of land within the SW ½ of Section 35, TlN, RIE, Eunkerhill Township, Ingham County, Michigan; as it is apparently peacefully occupied at present, and that we have found or set, as noted hereon, permanent markers to all corners and angle points of the boundaries of the parcels shown hereon, and the more particular descriptions of said parcels are as designated hereon.

This survey was performed with an error of closure not greater than a ratio of 1' in 5,000'.

This survey complies with the requirements of P.A. 132 of 1970.

Austin C. Williams

Registered Mand Surveyor

Mich. Registration No. 21275

1822

WILLIAMS

bisveying


1748 Okamos Rd Macon Michigan 48654 PM 15171 678 5113

	1	Ç Vê	84	130)			Į.		1/2		3	-		×		ν,	8		9-1	8	9	Ç.V	্	7	1	. 9
ű		Dŧ	151	Νe	JA.				, S	4		12	77	7.	Ŷ.	\$	ŧ.			2	1		(4)		Z	35
						(4) (4) (4) (4)	3000 3000	12/6			~210		277.61	12.75	T	men.	W			4.7			1. 12.			
ř.								3			A	80					V.		**	1	À	- 1				347
		2000	y (a		1	4.0	10/4	4.5	£.	10	. 1		7	×		2.0	×	701		7	()			re.	, ;	÷
			O.	St.		2													5					4.50	ij	
						20120								10	12								11			

Liber


CERTIFICATE OF SURVEY

RECORNED 960012551 G4/12/1996 09:14:08 REGISTER OF DEEDS Paula Johnson INSKYN COUNTY, MI



RECORDING SPACE

SCALE 1" = 200



WITNESSES:

SE Corner, Sec. 26, Bunkerhill Twp. 3/4" iron rcd in monument box 7/4 from red in monument box Witnessed by: N&T #18994 N. side utility pole, S 70° E, 71.46° N&T #17640 E. side 21" Walnut, N 40° E, 42.71° N&T #18994 N. side 21" Elm. N 55° E, 59.22' N&T #17840 E. side utility pole, N 25° W. 71.59°

S 1/4 Corner, Sec. 26, Bunkerhill Twp. 1/2" Iron rod with cap #20707 2.9'± south of scuth edge of asphalt Witnessed by Witnessed by: Witnessed by:
SW corner concrete brigde ralling, N 50° E, 39.82°
NW corner concrete bridgs ralling, Ecst, 64.22°
N&T #28414 S. side wood fence post, N 40° W, 52.49°
NW corner of NW bridge wing wall, North, 39.85° E 1/4 Corner, Sec. 26, Bunkerhill Twp. 1/2" iron rod, 6.3°± west of east edge of asphalt Witnessed by:

N&T #19834 W. side 32" Ock, N 35° E, 47.00'

N&T #28414 E. side 21" Ock, S 30' W, 84.18'

N&T #28414 S. side 15" Walnut, N 70' W, 29.14'

N&T #28414 E. side 24" Walnut, N 30' W, 44.67'

LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF
D= DEEDED
P= PLATTED
M= MEASURED
PROPERTY CORNER IRON
CONCRETE MONUMENT
O
FENCE LINE

FENCE LINE



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48654 PHONE (517) 676-9200

		(,	0200
SURVEY FOR:	ROGER STEVE	NS	
FIELD SURVEY:	T.Y. & T.S.	DATE:	3-26-96
DRAWN BY:	MJM	SHEET:	1 OF 2
SCALE:	1" = 200"	JOB NO.:	960538
	RE XXXX DW3		CWG.2855060



RECORDING SPACE

LEGAL DESCRIPTION

PARCEL A

A part of the SE 1/4 of the SE 1/4 of Section 26, T1N-R1E, Bunkerhill Township, A part of the SE 1/4 of the SE 1/4 of Section 20, IIN—KIE, BURKETHII TOWNSHIP, Ingham County, Michigan, described as beginning at a point on the centerline of Fitchburg Road, said line also being the South line of said Section N 90°00'00" W 349.99 feet from the SE Corner of said Section; thence continuing along the centerline of Fitchburg Road N 90°00'00" W 404.95 feet; thence N 00°17'16" W 297.00 feet; thence S 90°00'00" E 404.97 feet; thence S 00°17'05" E 297.00 feet to the point of beginning, containing 2.761 acres more or less and subject to the rights of the public over the existing Fitchburg Road, and any other easements or rights of way of

PARCEL B

A part of the SE 1/4 of the SE 1/4 of Section 26, T1N-R1E, Bunkerhill Township, Ingham County, Michigan, described as beginning at a point on the centerline of Fitchburg Road, said line also being the South line of said Section N 90'00'00" W 183.48 feet from the SE Corner of said Section; thence continuing along the centerline of Fitchburg Road N 90°00'00" W 166.51 feet; thence N 00°17'05" W 297.00 feet; thence S 90°00'00" E 166.51 feet; thence S 00°17'05" E 297.00 feet to the point of beginning, containing 1.135 acres more or less and subject to the rights of the public over the existing Fitchburg Road, and any other easements or rights of way of record.

PARCEL C

A part of the SE 1/4 of the SE 1/4 of Section 26, T1N-R1E, Bunkerhill Township ingham County, Michigan, Beginning at the SE Corner of said Section; thence N 90° 00'00" W along the centerline of Fitchburg Road, sold line also being the the South line of said Section 183.48 feet; thence N 00"17".05" W 297.00 feet; thence S 90"00" O0" E 183.48 feet to the centerline of Friermuth Road also being the East Section line; thence S 00"17".05" E 297.00 feet along Friermuth Road to the point of beginning, containing 1.251 acres more or less and subject to the rights of the public over the existing Fitchburg and Friermuth Roads, and any other easements or rights of way of record.

The basis of bearing for this survey is based on assuming N 00°00'00" W on the SOUTH Section Line.

ken

I hereby certify that I have surveyed and mapped the land above platted and/or described on March 21, 1996, and that the ratio of closure on the unadjusted field observation of such survey was 1/15,000, and that all the requirements of P.A. 132, 1970 have been complied with.

Maufice H. Mahieu P.S. #28414

Murue &

LEGEND


ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF ALL DIMENSIONS ARE IN I D= DEEDED P= PLATTED M= MEASURED PROPERTY CORNER IRON CONCRETE MONUMENT FI= FOUND IRON SI= SET IRON

FENCE LINE



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGA PHONE (517) 676-9200 MASON, MICHIGAN 48854

SURVEY FOR:	ROGER STEVE	NS	
FIELD SURVEY:	T.Y. & T.S.	DATE:	3-26-96
DRAWN BY:	MJM	SHEET:	2 OF 2
SCALE:	1" = 200"	JOB NO.:	960538
	SE XXXXLD#D		63063E3.0WC



LEGAL DESCRIPTION:

A part of the NE 1/4 of Section 35, T1N, R1E, Bunkerhill Township, Ingham County, Michigan, described as beginning at a point on the centerline of Fitchburg Road, said line also being the North line of said Section N 90°00'00" W 346.50 feet from the NE Corner of said Section; thence S 00°00'38" W 300.00 feet; thence N 90°00'00" W 99.00 feet; thence N 00°00'38" E 300.00 feet to the centerline of Fitchburg Road; thence along the centerline of Fitchburg Road S 90°00'00" E 99.00 feet to the point of beginning, containing 0.682 acres more or less and subject to the rights of the public over the existing Fitchburg Road, and any other easements subject to the rights of the public over the existing Fitchburg Road, and any other easements or rights of way of record.

The basis of bearing for this survey is based on assuming N 90°00'00" W on the NORTH Section Line.

I hereby certify that I have surveyed and mapped the land above platted and/or described on April 23, 1996, and that the ratio of closure on the unadjusted field observation of such survey was 1/15,000, and that all the requirements of P.A. 132, 1970 have been compiled with.

Maurice H. Mahieu P.S. #28414



LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF
DEEDED FI= FOUND IRON
SI= SET IRON

9



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 678-9200

DONNA LUKENICH							
TY - TS	DATE:	5-1-96					
MJM	SHEET:	1 OF 1					
1" = 100'	JOB NO.:	960568					
	TY - TS MJM	TY - TS DATE: MJM SHEET: 1" = 100' JOB NO.:					

RE: 9605385.DWG

DRAWING: 960568.DWG

The state of the s

WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 676-9200

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF D= DEEDED FI= FOUND IRON FI= FOUND IRON
SI= SET IRON P= PLATTED M= MEASURED
PROPERTY CORNER IRON
CONCRETE MONUMENT

FENCE LINE

SURVEY FOR:	JIM MYER	,_	
FIELD SURVEY:	ΤΥ	DATE:	9-8-97
DRAWN BY:	MLM	SHEET:	1 OF 2
SCALE:	1" = 100'	JOB NO.:	970641

THE PROPERTY OF THE PROPERTY O

WITNESSES:

East 1/4 Corner, Sec. 35, T1N, R1E, Bunkerhill Twp:, Ingham Co., Michigan Found Iron Rod in Road Witnessed by:
Nail in R:R. post, West, 30.32'
Pk. Nail in Telephone Pole, East, 24.30'
Pk. Nail in 24" Hickory, S.S.E. 87.18'

RECORDING SPACE

SE Corner, Sec. 35, T1N, R1E, Bunkerhill Twp., Ingham Co., Michigan Found "T" Iron 6" long 12" below asphalt surface.

Measured NW 81.2' to N&T W. side utility pole.

Measured SW 14.6' to centerline 24" Ash (recorded as Box Elder by Austin Williams). Measured SE 27.9' to centerline 24" Ash. Excavated 2.5'± below asphalt surface, found 8-10 smaller stones (4" dia.) in general area of "T" iron. excavated to clay, set 1/2" iron rod with cap #28414 in place of "T" iron. placed monument box and cover over 1/2" iron rod. Corner falls in approx. centerline of Freiermuth Road and south of centerline Baseline Road.

Witnesses:

N&T #28414 N. side 24" Ash, S62°E, 27.97'
N&T #28414 E. side 24" Ash, S20°W: 14:62'
N&T W. side utility pole, N36°W, 81.20'
N&T #28414 W. side utility pole, N8°E, 143.75'

Description as provided this office;
Beginning at a point in the center of Freiermuth Road where said road intersects S. line of the North 45 acres of the East 1/2 of the Southeast 1/4 of Section 35; thence North 21 rods to point of beginning thence West 18 rods; thence North 15.5 rods; thence East 18 rods; thence South 15.5 rods to point of beginning, Section 35, Town 1 North, Range 1 East, Bunkerhill Township; Ingham County, Michigan.

This parcel has been field surveyed and is more particularly described as; A part of the Southeast 1/4 of Section 35, T1N, R1E, Bunkerhill Township, Ingham County, Michigan, described as beginning at a point on the East line of Section 35, S00°15'24"E 890.23 feet from the East 1/4 Corner of said Section; thence continuing along the East line of Section 35 S00°15'24"E 255.75 feet; thence N89°56'12"W 297.00 feet; thence parallel with the East Section line of said Section N00°15'24"W 255.75 feet; thence S89°56'12"E 297.00 feet to the point of beginning, containing 1.744 acres of land more or less and subject to any easements or rights of way of record.

The basis of bearing for this survey is based on assuming S00°15'24"E on the East Section line.

I hereby certify that I have surveyed and mapped the land above platted and/or described on August 22, 1997, and that the ratio of closure on the unadjusted field observation of such survey was 1/15,000, and that all the requirements of P.A. 132, 1970 have been complied with.

Maurice H. Mahieu P.S. #28414



LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF
D= DEEDED FI= FOUND IRON
SI= SET IRON

-x-x-x-x



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 676-9200

SURVEY FOR:	JIM MYER		
FIELD SURVEY:	TY	DATE:	9-8-97
DRAWN BY:	MJM	SHEET:	2 OF 2
SCALE:	1" = 100'	JOB NO.:	970641

RE: XXXX.DWG


DRAWING 9705415.DWG

03/03/1999 13:52:59 REBISTER OF DEEDS Paula Johason INSSEM COUNTY 41

RECORDING SPACE


NW Cor., Sec. 36, T1N, R1E, Bunker Hill Twp. 3/4" bar in monument box 0.75' South of Fitchburg Rd. & 1.5' East of Freiermuth Rd. Witnesses: N&T #18994 N. side power pole, S70°E 71.46' N&T #17640 E. side 21" Wainut, N40°E 42.71' N&T #18994 N. side 21" Elm, N65°E 59.22' N&T #17640 E. side power pole, N25°W 71.59'


N 1/4 Cor., Sec. 36, T1N, R1E, Bunker Hill Twp. 1/2" bar in monument box centerline Fitchburg Rd. Witnesses: Spike NW side fence post, \$20°W 24.38' N&T #19834 W. side 8" Elm, \$N20°W 28.57' centerline double sign post, \$50°E 36.43' centerline sign post, \$N70°E 35.93'



W 1/4 Cor., Sec. 36, TtN, R1E, Bunker Hill Twp. T-bar in monument box centerline Freiermuth Rd. Witnesses:

N&T #17640 S. side power pole, East 23.70'
N&T #17640 S. side power pole, West 49.58'
N&T #17640 W. side 27" Hickory, S10°E 87.46'
N&T #28414 W. side 8" Ash, N40°E 67.90'





LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF
D= DEEDED FI= FOUND IRON
P= PLATTED SI= SET IRON
M= MEASURED

PROPERTY CORNER IRON CONCRETE MONUMENT **a** ŏ FENCE LINE



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 676-9200

SURVEY FOR:	MARK STEPHENS						
FIELD SURVEY:	TS	DATE:	11-25-98				
DRAWN BY:	MJM	SHEET:	1 OF 2				
SCALE:	1" = 100'	JOB NO.:	980686				
	RE: XXXX.DWG	****	DRAWING: 980686S.OWG				

RECORDING SPACE

The following is the legal description provided this office:

Commencing at a point 38 rods South of the Northwest corner of Section 36, T1N, R1E, Bunker Hill Township, Ingham County; thence East 26 rods; thence South 12 4/13 rods, thence West 13 rods; thence North 4/13 rod; thence West 13 rods; thence North 12 rods, to the point of beginning, except the N 20 feet of the West 6 1/2 rods.

Also except Commencing at a point 19 rods East and 30 rods 10 feet South of the NW corner of Sec. 36, T1N, R1E, Bunker Hill Township, Ingham County, Michigan, thence East 9 rods; thence South 7 rods 6 1/2 feet; thence West 2 rods; thence South 36 feet; thence West 115.5 feet; thence North 158 feet to place of beginning.

The above was field surveyed and divided into the following parcels.

Legal Descriptions:

PARCEL 1 — A part of the Northwest 1/4 of the Northwest 1/4 of Section 36, T1N, R1E, Bunker Hill Township, Ingham County, Michigan; described as beginning at a point on the West Section line S00°41'35"W 627.00 feet from the Northwest corner of said Section 36; thence N90°00'00"E 265.86 feet parallel with the North line of said Section 36; thence S00°41'35"W 203:08 feet parallel with said West line; thence S90°00'00"W 51.36 feet parallel with said North line; thence N00°41'35"E 5.08 feet parallel with said West line; thence S90°00'00"W 214:50 feet parallel with said North line to the West line of said Section 36; thence N00°41'35"E 198.00 feet along the said West line to the point of beginning, containing 1.214 acres of land more or less; and subject to any easements or rights of way of record.

PARCEL 2.— A part of the Northwest 1/4 of the Northwest 1/4 of Section 36, T1N, R1E, Bunker, Hill Township, Ingham County, Michigan; described as commencing at the Northwest 1/4 of said Section 36; thence S00°41'35"W 627.00 feet along the West line of said Section 36; thence N90°00'00"E 265.86 feet parallel with the North line of said Section 36 to the point of beginning; thence N90°00'00"E 47.64 feet parallel with said North line; thence S00°41'35"W 36.00 feet parallel with said West line; thence N90°00'00"E 115.50 feet parallel with said North line; thence S00°41'35"W 167.08 feet parallel with said West line; thence S00°41'35"E 203.08 thence: \$90°00'00"W 163:14 feet parallel with said North line; thence N00°41'35"E 203.08 feet parallel with said West; line to the point of beginning; containing 0.665 of an acre of land more or less, and subject to any easements or rights of way of record.

MAURICE H.

PROFESSIONAL

The basis of bearing for this survey is based on a survey recorded in Liber 2, Page 404, Ingham County Records.

thereby certify that I have surveyed and mapped the land above platted and/or described on November 20, 1998, and that the ratio of closure on the unadjusted field observation of such survey was 1/15,000, and that all the requirements of OF MICHAEL 132, 1970 have been complied with. P.A.


alle XMehrer Maurice H. Mahieu P.S. #28414

LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF

D= DEEDED FI= FOUND IRON
P= PLATTED SI= SET IRON D= DEEDED P= PLATTED M= MEASURED

PROPERTY CORNER IRON CONCRETE MONUMENT O FENCE LINE



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 676-9200

SURVEY FUR:	MARK STEPHENS		
FIELD SURVEY:	TS	DATE:	11-25-98
DRAWN BY:	MJM	SHEET:	2 OF 2
SCALE:	1" = 100'	JOB NO.:	980686

RE: XXXX.DWG

FOR: Chris Fuller Fuller Heating and Cooling 2338 N. Cedar Street Holt, MI 48842

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS RECORDED
POLARIS SURVEYING COMPANY L-8 P-685 2000-007953 SURV 11.00 02/25/2000 11:10A


LEGEND:

1. All dimensions are in feet and decimals thereof.

1/2" bar and I.D. cap have been placed at all points marked "o".

indicates government corner.
indicates not to scale.

5. _____ indicates described property line.
6. All bearings are relative and referenced to the East line of the Southeast 1/4 of Section 27 which is assumed to bear due North.



POLARI	S
SURVEYING	CO.

3081 Holt Road Mason, Michigan 48854 517/676-3630

fld. survey	RL	Nov 99	Sec. 27 , TlN , F	1E
drawn	RL	Nov 99	Co. Ingham	
sheet] of	2	Drawing number A-440		4a

SURVEYED DESCRIPTION OF PROPERTY:

A parcel of land located in the Southeast 1/4 of Section 27, Town 1 A parcel of land located in the Southeast 1/4 of Section 27, Town 1 North, Range 1 East, Bunker Hill Township, Ingham County, Michigan, the surveyed boundary of said parcel being described as Beginning at the Southeast corner of said Section 27; thence North 89°52′30" West along the South line of said Section 27 a distance of 363.00 feet; thence North 00°00′00" East parallel to the East line of said Section 27 a distance of 858.00 feet; thence South 89°52′30" East parallel to the South line of said Section 27 a distance of 363.00 feet to the East line of said Section 27; thence South 00°00′00" West along the East Line of said Section 27 a distance of 858.00 feet to the point of beginning: said Section 27 a distance of 858.00 feet to the point of beginning; said parcel containing 7.150 acres; said parcel subject to the rights of the public across Fitchburg Road and across Haynes Road; said parcel subject to all other easements and restrictions of record.

WITNESSES TO GOVERNMENT CORNERS:

Southeast corner Section 27, T1N, R1E. 1/2" pipe in monument box.

Liber 8, Page 118.

Southeast corner concrete foundation #1455 mag. az. 320°, 80.51'

Nail and tag #18994 S. side 20" cherry mag. az. 292°, 91.64'

Set galvanized nail and 1 1/2" aluminum tag stamped "PS 18998 WITNESS"

E: side 30" walnut mag. az. 209°, 59.58' Set galvanized nail and 1 1/2" aluminum tag stamped "PS 18998 WITNESS" W. side 15" cedar mag. az. 162°, 57.22'

South 1/4 Corner Section 27, T1N, R1E. 1 1/2" pipe. Liber 8, Page 118. Found nail and tag #18994 E. side 24" maple mag. az. 190°, 25.17' Found nail and tag #18998 S. side 12" maple mag. az. 145°, 33.81' Found nail and tag #18998 S. side 10" dead tree mag. az. 126°, 24.30' Set galvanized nail and 1 1/2" aluminum tag stamped "PS 18998 WITNESS" S. side %10 " ash mag az. 77°, 25.51'

East 1/4 Corner Section 27, Tin, Rie. Found concrete monument in monument box. Liber 4, Page 273.

Top of angle iron fence post mag. az. 105°, 34.14'

Centerline of East end 36" C.M.P. mag. az. 75°, 25.75'

Centerline of West end 36" C.M.P. mag. az. 288°, 25.01'

Set galvanized nail and 1 1/2" aluminum tag stamped "PS 18998 WITNESS"

W. Side 48" elm mag. az. 12°, 217.00'

CERTIFICATE OF SURVEY:

I hereby state to the parties named hereon that I surveyed a tract of land previously described as:

A parcel in the Southeast corner or the southeast ... 27, Town 1 North, Range 1 East; 104 rods North and South by 22 rods Section 27; thence North 32 rods; thence West 10 rods; thence South 32 rods; thence East 10 rods to beginning.

also: Beginning in the Southeast corner of Section 27, Town 1 North, Range 1 East, said two acres running 10 rods East and West by 32 rods North and South, Township of Bunker Hill, Ingham County,

and I have divided a parcel of land from said tract and that I have set permanent markers to all corners of said parcel and that the more particular surveyed description of said parcel is as indicated hereon. This survey complies with the requirements of P.A. 132 of 1970 as amended.

This survey was performed with an error of closure no offeater than a ratio of 1 in 40,000 based upon unadjusted field datum.


m. Luck 11/22/99 Ronnie M. Lester, Professional Surveyor #18998

an Ho RONNIE M. ŝ 샾 LESTER PROTESSIONAL SUNVEYOR eto. Podes

POLARIS SURVEYING CO.

3081 Holt Road Mason, Michigan 48854 517/676-3630

fld. survey	RL	Nov 99	Sec. 27 ; T	IN,RIE
drawn	RL	Nov 99	Co. Ingham	
sheet 2 of	2	Drawing	number /	4-4404a




Legal Description:

A part of the Northwest 1/4 of Section 36, T1N, R1E, Bunkerhill Township, Ingham County, Michigan, described as beginning on the West Section Line at a point N00°00'00"E 382.84 feet from the West 1/4 Corner of Section 36; thence N00°00'00"E 100.00 feet; thence N90°00'00"E 214.50 feet; thence N00°00'00"E 108.50 feet; thence S90°00'00"W 208.50 feet; thence S90°00'00"W 425.00 feet to the point of beginning, containing 1.50 acres of land more or less and subject to any easements or rights of way of record.

The basis of bearing for this survey is based on assuming N00°00'00"E on the West Section line.

I hereby certify that I have surveyed and mapped the land above platted and/or described on July 18, 2002, and that the ratio of closure on the unadjusted field observation of such survey was 1/15,000, and that all the requirements of P.A. 132, 1970, as amended have been complied with.

MILL urice H. Mahieu P.S. #28414



LEGEND

ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF D= DEEDED FI= FOUND IRON SI= SET IRON

P= PLATTED
M= MEASURED
PROPERTY CORNER IRON
CONCRETE MONUMENT FENCE LINE



WOLVERINE ENGINEERS & SURVEYORS, INC 312 NORTH ST. MASON, MICHIGAN 48854 PHONE (517) 676-9200

<u></u>			
	ALBERT MATY	ZIUS	
FIELD SURVEY:	HR & BD	DATE:	7-24-02
DRAWN BY:	МЈМ	SHEET:	1 OF 1
SCALE:	1" = 100'	JOB NO.:	02-0514
	RE: XXXX.DWG		DRAWING: 020514S.DWG